

5.	Nairobi Campus KeMU Towers building	KeMU towers floor 8 Wireless Access Points (PoE wall/Ceiling mount With Security Cage):	two (2) instead of 1 as indicated on the tender
6.	Nairobi Campus KeMU Towers	towers floor 12 Wireless Access Points (PoE wall/Ceiling mount With Security Cage)	two (2) instead of 1 as indicated on the tender

7.

Meru Main
campus

Men and women hostels uplink
fiber

Install a multimode fiber link
connecting the Men& women
Hostels approximate 40 m

Capacity: 3000VA / 2700W

Battery Backup Time: Approximately 2 hours on moderate load, with options for External battery packs to extend runtime.

True sine wave output, high efficiency, network management for remote Monitoring and AVR (Automatic Voltage Regulation) to handle irregular power.

Rack Size: 2U to 3U

All other terms and conditions remain the same

PROCUREMENT DEPARTMENT,

KENYA METHODIST UNIVERSITY